KEY

- Site Boundary
- Existing planting to eastern boundary of site
- Proposed native infill planting to existing boundary planting
- Proposed wet meadow planting Emorsgate EG8 Wet Meadow Grass Mix
- Public right of way
- Overhead power cables

Proposed Native Infill Planting

Plant Name	Specification	% mix
Acer campestre	*40-60cm, 1+1 transplant, bareroot*	20
Corylus avellana	*40-60cm, 1+1 transplant, bareroot*	20
Cornus sanguinea	*40-60cm, 1+1 transplant, bareroot*	10
Crataegus monogyna	*40-60cm, 1+1 transplant, bareroot*	15
Salix caprea	*40-60cm, 1+1 transplant, bareroot*	20
Sorbus aucuparia	*40-60cm, 1+1 transplant, bareroot*	15

PHASE ONE

PHASE TWO

270m²

220m²

Native infill planting to existing boundary planting

Existing Public Right of Way

Existing planting

Overhead power cables

REVISIONS				
Rev.	Description	Date	By	Chk'd
-	-	-	-	-

PLANNING

client: QUINTON_HAZELL_ENTERPRISE_PARC
project: LAND_AT_QUINTON_HAZELL_ENTERPRISE_PARC
drawing title: LANDSCAPE_STRATEGY

land | studio

scale: @ A2 1:500
date: 17.12.2021
drn: HA
chk'd: SR

001
/

CAD FILE NAME: C:\Users\Hamzah Akhoon\Dropbox (Land Studio)\05 Projects\227 Quinton Hazell, Mapledale\01 CAD\227_QHZ_0700.dwg

© This drawing is the property of Land Studio and the information can only be reproduced with their prior permission

Original paper size (A2) 420x594mm